



Contegra - 717

Project Overview



Client:
Contegra Construction

Location:
Edwardsville, IL

Completion Date:
June 2016

Description:

717,000 SF Spec Warehouse
Job started as a Spec Building and was completed for Amazon
Gateway Commerce Phase 3 Work happened as the same time as this Building
9,500 LF of Silt Fence
300,000 CY of Cut / Fill
6,500 LF of Storm Sewer – 15" – 54"
800 LF of Sanitary Sewer
65,000 SY of 12" Depth Lime Stabilization – 7% Rate
80,000 SY of 24" Depth Lime Stabilization – 7% Rate
Over 1,000 Tons of Drying Lime for Engineered Fill