



## Contegra - Lot 9B

### Project Overview



**Client:**  
**Contegra Construction**

**Location:**  
**Edwardsville, IL**

**Completion Date:**  
**February 2018**

### **Description:**

- 6,000 LF of Silt Fence**
- 327,000 CY of Cut / Fill**
- 57,000 SY of 12" Depth Lime Stabilization – 7% Rate - Code L**
- 66,000 SY of 24" Lime Stabilization – 7% Rate – Code L**
- 5,500 LF of Storm Sewer – 12" – 48"**
- 800 LF of Sanitary Sewer**
- Over 2,500 Tons of Drying Lime for Engineered Fill**