



# Exeter Building

## Project Overview



**Client:**  
**Meridian Design Build**

**Location:**  
**Edwardsville, IL**

**Completion Date:**  
**December 2019**

### Description:

- 475,000 CY of Cut / Fill
- 675,000 SF Warehouse
- Grading for a future 1.1M SF Warehouse Pad
- Grading and Lime Stabilization for INNER PARK Road Extension
- 7000 LF of Storm Sewer – 12” – 48” RCP
- 2200 LF of Sanitary Sewer 6” – 12”
- 13’ Deep Fiberglass Lift Station Complete
- 4,400 LF of 12” Watermain Loop for New Park
- 4,800 LF of Dual 4” SCH 40 Conduit for Future Electrical Work
- 87,000 SY of 12” Depth Lime Stabilization – 7% Code I
- 75,000 SY of 32” Depth Lime Stabilization – 7% Code I
- Over 4,500 Tons of Drying Lime Installed for Engineered Fill
- 7,000 LF of Silt Fence