



# Fairmont City Terminal Lift Station

## Project Overview



**Client:**  
**Village of Fairmont City**

**Location:**  
**Fairmont City, IL**

**Completion Date:**  
**June 2018**

### Description:

- 22' Deep 10x10 Pre-Cast Wet Well
- (3) 30 HP Fairbanks Pump for Lift Station
- Generator for Lift Station
- Dewatering for High Water Table
- 390 LF of 20" Jack and Bore Casing for Force main
- 1500 LF of 12" Force main
- 100 LF of 12" Fore main installed in 27" VCP Pipe under a canal