



Levee Certification– Package 7A

Project Overview



Client:
Southwestern IL Flood
Prevention District

Location:
Alton, IL

Completion Date:
June 2015

Kamadulski was awarded the contact as the Prime Contractor. Project managed the construction of a Soil Bentonite Cutoff Wall by slurry trenching method along the riverside toe of the existing east bank of the Mississippi River. The total length of the slurry wall was approximately 1,600 feet. Scope of work consisted of degrading approximately 30,000 cubic yards of existing levee, constructing 1,700 linear feet of stabilized work platform 50 feet wide, and place back specified impervious clay cap material of 30,000 cubic yards. Kamadulski worked extensively with the Alton Marina and the City of Alton in the restoration of roads, parking lots, and the utility and infrastructure conflicts. The award Prime Contract on this project was \$3.5 million dollars completed successfully.