



Republic Services Cell 7-10

Project Overview



Client:
Republic Services

Location:
Roxana, IL

Completion Date:
December 2020

Republic Services awarded us a multi-million dollar contract to construct (5) Cells 7-8-9-10-10S. These projects are all similar due IEPA landfill construction requirements. These projects combined totaled approximately 465,000 cubic yards of structural fill excavated and placed, 175,000 cubic yards of imported clay cap liner installed per specifications, temporary roads for borrow pits, and the dewatering of all excavations. All structural fill and imported clay cap liner material comes from Mississippi River Bottoms near this project. Approximately 1.5 million dollars of leachate pipe and infrastructure was installed by our crews as well on this particular project. IEPA requires strict installation procedures for this infrastructure work. This project was 100% self-performed by Kamadulski crews and was completed successfully in 2020.